Harsh Goel¹, Priyanshu Sharma¹, Dr. Tanmay Gupta¹

Turkish Online Journal of Qualitative Inquiry (TOJQI) Volume 12, Issue 3 ,July 2021 : 2691 - 2701

Research Article

Hilly road mapping and holistic management to visualize and plan construction: A case study in Himalayan region

Harsh Goel¹, Priyanshu Sharma¹, Dr. Tanmay Gupta¹

¹Civil Engineering Department, Jaypee University of Information Technology, Waknaghat 173234 Solan, H.P India

Abstract:

Traffic conjunction is quite common now a days even in hilly terrain, due to several factors such as increasing tourism/industrialism, blocking of roads due to natural calamities, accidents etc. which tend to seize roads for hours. Such natural or manmade disastrous often results in roads with high traffic densities, prompting road blockage for quite a long time. The solution for such circumstance is often done via road widening or construction of an alternate road. Present case study focuses on construction of an alternate hilly road from Lansdowne to Palkot in Uttarakhand stretching 4.6 Kms in the Himalayan region. Based on the survey performed at the construction site an impactful visualization and mapping is done using surfer software in 3D and 2D. Furthermore, detailed road construction and management of various constructions activities is planned based on well-known construction management principle established by ministry of road transport India and implemented using Primavera and MS-Excel. Such holistic management of construction activities yielded in efficiency of 3 months from total sanctioned schedule time of 18 months for completion of the project. At the end based on latest BOQ as per CPWD, Uttarakhand a financial estimation of the project is also provided. **Keywords:** *construction management, road visualization, 3D and 2D plots, road blockage, management of*

roads, financial estimation

Introduction:

Roads are one of the most essential commodities required in present day and age to facilitate transportation and access to different places. Any countries overall development majorly depends on the robust road network, which can safely provide passage to high traffic volumes under all circumstances [1-3]. There are a number of types of roads that are being prepared in a country to fulfill different types of requirements according to its width, location, economy, traffic type, rigidity, topography and material. Any good road network has various elements in it, beginning with National Highways (NH) which are constructed to connect all the major cities to the capitol of the country and often are spread throughout the country. State Highways (SH) on the other hand are developed to associate every one of the primary pieces of states inside it. These can be called as second fundamental streets and are finally interface with NH. District Roads are built to interface every one of the little urban communities inside the region to business sectors and to associates the two of them to the public roadways and NH. Village Roads are constructed to connect all the nearby villages to each other and all of them to the district roads. Rural areas have completely different variant of roads to attach farms with their respective town or any city which are sometimes even unpaved. Such roads take farm products produced to city markets and children to school [4].

Hilly road mapping and holistic management to visualize and plan construction: A case study in Himalayan region



Figure: 1 showing NH, SH, District Road and Village road respectively

However, many a times it is observed that roads are not able to fulfill the traffic demands of certain routes due to rapid industrialization and urbanization. Therefore, governing authorities are taking necessary steps in developing countries like India to avoid high traffic volumes especially of critical pathways. Constructing a new road is modern alternative for this problem, modern because of the enhancement in construction technology now a days has made construction procedure very swift and convenient which was not the case in last decades. New construction not only improves traffic safety but also the capacity which is essential for a nations progress [5-8]. Present study focusses on case study of construction of a State Highway Road from Lansdowne to Palkot region in Uttarakhand. This site is constituted of mountainous terrain type of land amongst the foothill of Himalayas. Paper presents an efficient way to visualize the hilly road from 3D and 2D perspective along with competent construction management and planning which proposes efficiency of 3 months from total sanctioned time. Finally, paper also presents detailed financial breakup of the project as per the latest bill of quantities taken from Central Public Works Department Uttarakhand, Government of India.

Geotechnical review of the site:

The whole length of road being prepared during this project is estimated to be 4.6 Kms long and planned to be black topped on its whole surface.

Topography and soils:

Uttaranchal State is essential for the Western Himalaya and isolated into four zones agreeing height in particular, the Tarai-Bhabar-Shivalik (Sub-Himalayas) with elevation going from 750-1,200meters, Lesser-Himalayas between 1,000 – 3,500 meters, Greater-Himalayas between 3,500-4,800m with snow-line ascending to 5,400m and Trans Himalaya (Tethys) averaging 5,300m. By and large, the district is topographically and pedologically temperamental and inclined to slides and disintegration. Soils of the Uttarakhand Himalayas overall are very shallow, seriously impregnated with un-endured pieces of parent rocks.

Nature of soils of the area have been framed either through paedogenetic measures or they are shipped soils. The paedogenetic soils are the one which have shaped due to long time of exposedness to air offices, physical and synthetic enduring and rock slides

Site overview:

This venture imagines broadening of streets in Pauri Garhwali District of Uttarakhand state. Under this venture single path streets are altered as twofold path streets. The undertaking incorporates the improvement streets associating Jaswantdwar in Lansdowne district to Palkot.

Figure 2 shows the broad map of the region in which the road is planned to be constructed and the highlighted blue colored curved line depicts the road described above:



Fig 2- Broad map of the geo-spatial location of the road considered in the case study


Surveying of the Project Site:

Surveying is the science to determine earthbound or 3D places of focuses and moreover points and furthermore the length between these foci. These focuses normally lie on the outside of the earth, and these focuses are regularly familiar with fabricate guides and limits for possession, areas, such as corner building or the surface area of sub-surface alternatives, or totally various capacities needed by Govt. or law, similar to deals of property. Also arranging and execution of most assortments of development need it. It's moreover utilized in transport, correspondences, planning, and furthermore the meaning of legitimate limits for land ownership. A brief overview of survey done for the project is presented below:

Step by step measurements via Total station theodolite:

- 1. Set up the Total Station at Base point (Jaswantdwar) and leveling it.
- 2. Now with help of compass see the north direction on total station and input the northing angle as 0.
- 3. Now using Handy GPS, Northing, Easting and Elevation values of Jaswantdwar inserted in Total Station that are 235975, 235980 and 1508m respectively.
- 4. As Station coordinates are inserted, now putting Back Sighting Northing, Easting and Elevation as 0, 0 and 0 respectively.
- 5. Now input the height of instrument and height of prism pole in total station.
- 6. Now sight the prism that should be around 30m from instrument. Take the readings of Northing, Easting and Elevation at right, left and center of the road, marks those points by Marker and save them.
- 7. Now replace the Total Station on right/left half of the street and information the station facilitates estimated above and back sights the left/right.

8. Take next arranges of right, left and focus and save them. Rehash the above advances and save the directions.





3D and 2D Mapping of the Road via Surfer

Surfer is an amazing forming, gridding, and surface planning bundle for researchers, architects and academicians to produce maps rapidly without any problem. Present study employs the total station surveying data in form of chainage, easting, nothing and finished road level elevation to produces distribution quality guides. Surfer effectively impart both straight forward and complex spatial information which is extensively used for the present project.

STEP 1: Creation of grid data






Table 1 Step by step modelling in surfer:





STEP 4: Grid file creation

🖣 vn 🖞

STEP 5: Choice for a contour map








N .

0 0 0 4 1 0 0 1 0 0

STEP 8: Selection of base map option

STEP 9: Grid file date selection

STEP 6: Selecting the grid data for



For the present project, the roads visualization along with the surrounding topology can be visualized in high quality 3D and 2D contour plots as shown in Figure 4 and Figure 5 respectively along with the elevation. A plot showing the location of retaining walls (in red color), breast walls (in green color) and toe wall (in blue color) is also generated via Surfer and is shown in Figure 6.




Fig 3- 3D geometry plot of the hilly road under investigation obtained via surfer

Hilly road mapping and holistic management to visualize and plan construction: A case study in Himalayan region




Fig 5-2D geometry plot of the hilly road under investigation obtained via surfer




Fig 6- Location of Retaining walls (Red), Breast walls (Green) and Toe walls (Blue) along the road plotted in Surfer

Road Construction Management and Estimation:

The estimation of whole construction was done on the basis of latest BOQ and SOR of Uttarakhand using MS-Excel. Various parameters considered and associated cost are depicted in Table 2.

Table 2 Cost estimation as per later BOQ and SOR of Uttarakhand, India for the investigated hilly road:

S.n Description	Labour Unit	Labour type	Per Quantity	Unit s	Area to cover	Availabl e labour		Cost of 1 labour per day INR	
1.0 Jungle clearance including cutting	30	labour man	2000	sq m	27161.9	28	14.55	750	305571.71


1 down trees					3				
Rough excavation in soil/soil				,	72200 7				
 1.0 mixed with small boulders using 2 mechanical means 	1	excavator	1000	cu m	23328.7 7	1	23.32	5000	116643.85
	1	labour man	1000	cu m	,	1	23.32	2000	110015.05
1.0 Rough excavation in soft rock		including		(51881.8				
3 requiring blasting	15	supervisor	1000	cu m	7	35	26.52	900	835405.24
disposal of excavated material by				(51881.8				
any means to dumping location	1	Truck	2000	cu m	7	2	15.47	2000	61881.87
1.0 Rough Excavation in hard rock by		~					10.00	1000	
4 drilling with compressor	2	Compressor	800	cu m 4	4372.56	1	10.93	4000	43725.6
Dough avapuation in asft reals		labour man							
Rough excavation in soft rock requiring blasting	15	including supervisor	1000	cu m	4372.56	30	2.18	900	59029.56
disposal of excavated material by	15	supervisor	1000	cu III -	+372.30	50	2.10	700	57027.50
any means to dumping location	1	Truck	2000	cu m 4	4372.56	3	0.72	2000	4372.56
1.0					49817.9	-			
5 compaction by mechanical means	1	compactor	2000	cu m	8	1	24.90	4500	112090.45
Earthwork in embankment by				4	49817.9				
filling with earth	30	labour man	1000	cu m	8	30	49.81	750	1120904.55
									2659625.40
2.0 Construction of Kerb and Channel	30	labour man	1000	r/mtr 4	4494.03	45	2.99	1000	134820.9
 type road side Drain Construction of Culvert 2 Mtr 									
2.0 Construction of Culvert 2 Mtr2 Span	30	labour man	3	nos.	17	39	4.35	1000	170000
2.0 Construction of Culvert 3 Mtr									
3 Span	30	labour man	2.5	nos.	8	30	3.2	1000	96000
2.0	20	1 1				10	2	1000	100000
$\frac{2.6}{4}$ Construction of Culvert 6 Mtr span	30	labour man	1	nos.	4	40	3	1000	120000
2.0 Construction of RRM Breast Wall	30	labour man	100	R/M	680	50	4.08	1000	204000
5 2.00 Mtr height	50	luooui mun	100	tr	000	50	4.00	1000	204000
2.0 Construction of RRM Breast Wall	30	labour man	75	R/M	280	35	3.2	1000	112000
6 3.00 Mtr height				tr					
2.0 Construction of RRM Retaining7 Wall 2.00 Mtr height	30	labour man	100	R/M	440	40	3.3	1000	132000
2.0 Construction of RRM Retaining				tr R/M					
8 Wall 4.00 Mtr height	30	labour man	60	tr	1200	45	13.33	1000	600000
2.0 Construction of RRM Toe Wall	20	1 1	100	R/M	000	10	5 5 0	1000	2 40000
9 1.00 Mtr Height	30	labour man	100	tr	800	43	5.58	1000	240000
2.1 Construction of RRM Toe Wall	30	labour man	50	R/M	700	40	10.5	1000	420000
2.1 2.00 Mtr Height	50	labout illali	50	tr	700	40	10.5	1000	420000
2.1 Construction of RRM Parapet Wall	30	labour man	500	R/M	1372	44	1.87	1000	82320
1	20		000	tr	1072		1107	1000	02020
Plastering	30	labour man	400	R/M	1372	45	2.28	1000	102900
2.1 Providing & Fixing ordinary KM				tr					
2 stone	30	labour man	2	nos.	5	45	1.66	1000	75000
2.1									
$\frac{2.1}{3}$ Providing & Fixing sub KM stone	30	labour man	10	nos.	18	45	1.2	1000	54000
2.1 Providing/Fixing of delineator	20	labour	50	n 00	144	16	1 07	1000	96400
4 (900 mm)	30	labour man	50	nos.	144	46	1.87	1000	86400
									2629440.9

Preparation of sub-grade in SMB								
3.0 by excavating upto 20 cm avg depth	30	labour man	1000	Sqm 5278.32	50	3.16	900	142514.64
consolidating with power roller	1	power roller	1000	Sqm 5278.32	2	2.63	12000	63339.84
Watering	30	labour man	1000	Sqm 5278.32	45	3.51	900	142514.64
3.0 Preparation of sub-grade in SR by2 excavating upto 20 cm avg depth	30	labour man	500	Sqm 13150	45	17.53	900	710100
consolidating with power roller	1	power roller	1000	Sqm 13150	2	6.57	12000	157800
disposal of surplus material by any mean to dumping location	1	Truck	2000	cu m 13150	4	1.64	2000	13150
3.0 Preparation of sub-grade in HR by3 excavating upto 20 cm avg depth	30	labour man	500	Sqm 1962.84	44	2.67	900	105993.36
consolidating with power roller	1	power roller	1000	Sqm 1962.84	2	0.98	12000	23554.08
disposal of surplus material by any mean to dumping location	1	Truck	2000	cu m 1962.84	4	0.24	2000	1962.84
GSB 15 cm thick (compacted) with 3.0 stone aggregate including disposal 4 of surplus material by any mean to dumping location	1	Truck	2000	cu m 4	4	2.49	2000	19978.34
Watering	30	labour man	1000	Sqm 19978.3 4	44	13.62	900	539415.18
Compaction with power vibratory roller	1	power roller	1000	Sqm 19978.3 4	2	9.98	12000	239740.08
3.0 5 Providing, laying, spreading stone aggregate grading as per Table- 400-13	30	labour man	600	Sqm ^{18635.3} 5	45	20.70	900	838590.75
compacting graded stone aggregate with power vibratory roller	1	power roller	1000	Sqm 18635.3 5	2	9.31	12000	149082.8
premixing the material with water to OMC in mechanical mix (Pug Mill)	1	pug mill	1500	Sqm ^{18635.3} 5	2	6.21	10000	124235.66
laying in uniform layers in sub base/base course on a well prepared base	30	labour man	600	Sqm ^{18635.3} 5	45	20.70	900	838590.75
3.0 6 to OMC in mechanical mix (Pug Mill)	1	pug mill	1500	Sqm 37270.7 1	2	12.42	10000	248471.4
laying in uniform layers in sub base/base course on a well prepared base	30	labour man	600	Sqm 37270.7 1	44	42.35	900	1677181.95
compacting graded stone aggregate with power vibratory roller	1	power roller	1000	Sqm 37270.7 1	2	18.63	12000	447248.52
3.0 Providing and laying 50 mm thick7 DBM layer	30	labour man	500	Sqm 17623.8 6	45	23.49	800	845945.28
Rolled to the required specification	1	power roller	1000	Sqm 17623.8 6	2	8.81	12000	211486.32
mix composition requirement as per Table - 500-8/9/10	1	pug mill	700	Sqm 17623.8 6	2	12.58	10000	251769.42
3.0 Providing and laying 30 mm thick8 BC on bituminous concrete layer	30	labour man	500	Sqm 17623.8	45	23.49	900	951688.44
8 BC on bituminous concrete layer mix composition requirement as	1	pug mill	700	6 Sqm 17623.8	2	12.58	10000	251769.42
Possion requirement us	-	r -8			-			

per Table - 500-8/9/10 3.0 Providing and applying Prime Coat	30	labour man	500	6 Sqm ^{17292.3}	45	23.05	900	933787.44
9 with bitumen emulsion g clearing of road surface & spraying primer using mechanical	1	sprayer	2000	6 Sqm ^{17292.3} 6	2	4.32	7000	60523.26
means Providing and applying tack coat 3.1 with bitumen emulsion using emulsion pressure distributor	1	emulsion pressure distributor	5000	Sqm 35247.7 3	2	3.52	8000	56396.36
surface cleaning	1	mechanical broom	5000	$\operatorname{Sqm} \frac{35247.7}{3}$	2	3.52	5000	35247.73
3.1 Provisioning and Providing road2 marking with thermoplastic paint	30	labour man	1000	Sqm 1643.41	45	1.09	800	39441.84

10121520.37


Furthermore, in order to do efficient scheduling and management of the whole construction phase Primavera software was employed which helps in planning and control of project schedule from cost to time. For current project, construction phases can be presented using above mentioned activities and costs in Primavera as follows:



	Network diagram ci	reation					Resou	irce allo	cation		
	Filter, Al Activities					esources					
Anna -						Activities Resources Projects					
						✓ Display: All Resources					
						Resource ID E Price / Unit Resource I	lame	Resource Type	Unit of Measure Prim	ry Role Default U	Units / Time
					– i	1 Re500.00/d unskilled la	bour	Labor			1/
						2 Rs800.00/d skilled labo	ur	Labor			1/
						A 3 Rs1.000.00/d labour with	supervisor	Labor			1.
						3 Rs1,000.00/d labour with 4 Rs5,000.00/d excavator	100000	Nonlabor			1
						4 5 Rs2,000.00/d truck		Nonlabor			1
						6 Rs4.000.00/d compresso		Nonlabor			1
						7 Rs8,000.00/d power role		Nonlabor			1
						🚯 8 Rs6,000.00/d pug mil		Nonlabor			1.
	<u> </u>					4 9 Rs5.000.00/d emulsion p	essure distributor	Nonlabor			1/
	1					10 Rs3,000.00/d mechanica		Nonlabor			1
						11 Rs4,500.00/d compactor		Nonlabor			1
						 12 Rs5,000.00/d sprayer 		Nonlabor			1
						 13 Rs70.00/unit deset 		Materia			8
						To Hardowark accord		in the state			.0
						General Codes Details Units & Prices Roles Notes					
	Project Layout				1		Pı	oject Co	ost		
tivities	Project Layout						Pı	oject Co	ost		
	Project Layout						Pı	roject Co	ost		
c tivities Ro	esources Projects sic Schedule Layout Fitter: All Activities				1	Filter: All Activities		5			
tivities R Layout: Class ivity ID	esources Projects sic Schedule Layout Fiter: All Activities Activity Name	Original Rem	ration Co	ule % Start		Fiter-All Activities Resources	Budgeted Labor Cost	Budgeted Nonlabor Cost	Budgeted Total Cost	Calendar	Total
tivities R Layout: Class ivity ID SHIVAL	esources Projects aic Schedule Layout Fiter: All Activities Activity Name	Original Duration 469	tration Co	nplete	20 14-1	Resources	Budgeted Labor Cost Rs:10,865,350.00	Budgeted Nonlabor Cost Rs4,649,500.00	Budgeted Total Cost Rs19,594,450.00	Standard 5 Day Workweek	Total
Layout: Class with ID SHIVAL FORM	esources Projects sic Schedule Layout Filter: All Activities Activity Name IK IATION WORKS	Original Rem Duration Du 469 140	140 Co	nplete 1.94% 03-Aug- 100% 03-Aug-	20 14-1 20 11-1	Resources	Budgeted Labor Cost Rs10,865,350.00 Rs2,215,750.00	Budgeted Nonlabor Cost Rs4,649,500.00 Rs465,500.00	Budgeted Total Cost Rs19,594,450.00 Rs3,277,650.00	Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R/ Layout: Class Ivity ID SHIVAL SHIVAL FORM A100	esources Projects aic Schedule Layout Fiter: All Activities Activity Name IK IATION WORKS 0 JUNQLE CREARANCE	Original Rem Duration Du 469 140 21	ration Co 469 4 140 21	nplete 1.94% 03-Aug- 100% 03-Aug- 100% 03-Aug-	20 14-1 20 11-1 20 21-1	Resources	Budgeted Labor Cost Rs10,885,350.00 Rs2,215,750.00 Rs295,750.00	Budgeted Nonlabor Cost Rs4,649,500.00 Rs465,500.00 Rs0.00	Budgeted Total Cost Rs19,594,450.00 Rs3,277,650.00 Rs295,750.00	Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R Layout: Class vity ID SHIVAL SHIVAL FORM A100 A102	esources Projects sic Schedule Layout Fiter: All Activities Activity Name IK IX	Original Rem Duration Du 140 21 27	ration Co 459 4 140 21 27	Inplete 03-Aug 100% 03-Aug 100% 03-Aug 100% 03-Aug 100% 25-Sep	20 14-1 20 11-1 20 21-1 20* 20-1	Resources	Budgeted Labor Cost Rs10,865,350.00 Rs2,215,750.00 Rs295,750.00 Rs0.00	Budgeted Nonlabor Cost Rs4,649,500.00 Rs465,500.00 Rs0.00 Rs243,000.00	Budgeted Total Cost Rs19,594,450.00 Rs3,277,650.00 Rs295,750.00 Rs545,400.00	Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R Layout: Class wity ID SHIVAL SHIVAL FORM A100 A102 A103	esources Projects aic Schedule Layout Fiter: All Activities Activity Name IK INTOIN WORKS UNIQUE CREARAIRCE INDUGLE CREARAIRCE IROUGH EXCAVATION OF SOFT SOL	Original Rem Duration D 469 140 21 27 11	ration Co 469 4 140 21 27 11	nplete 1.94% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 03-Nov-	20 14-1 20 11-1 20 21-J 20* 20-J 20* 12-0	Resources U unakiled labour U unakiled labour excavator, truck, diesel truck, compressor, labour with supervisor, d	Budgeted Labor Cost Rs10,885,350.00 Rs2,215,750.00 Rs295,750.00	Budgeted Nonlabor Cost Rs4,649,500.00 Rs465,500.00 Rs0.00 Rs243,000.00 Rs110,000.00	Budgeted Total Cost Rs19,594,450.00 Rs3,277,650.00 Rs545,400.00 Rs594,000.00	Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek	
ivities R Layout: Class vity ID SHIVAL FORM A100 A102 A103 A101	esources Projects as Schedule Layout Fiter: All Activities Activity Name UK INTON WORKS 0 ROUGH EXCAVATION OF SOFT SOL	Original Duration Rem Duration 489 140 21 21 27 11 24 24	ration Co 469 4 140 21 27 11 24	Inplete 1.94% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 03-Nov- 100% 24-Aug-	20 14-1 20 11-1 20 21-1 20* 20-1 20* 12-0 20* 15-0	Resources O Unskilled labour excavator, truck, diesel truck, compressor, labour with supervisor, d jabour with supervisor	Budgeted Labor Cost Rs10,665,350.00 Rs2,215,750.00 Rs295,750.00 Rs330,000.00	Budgeted Nonlabor Cost Rs4,649,500.00 Rs465,500.00 Rs0.00 Rs243,000.00	Budgeted Total Cost Rs19,594,450.00 Rs3,277,650.00 Rs295,750.00 Rs545,400.00	Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek Standard 5 Day Workweek	
Layout: Class wity ID SHIVAL A1001 A1021 A1031 A1041 A1041	Esources Projects sic Schedule Layout Fiter: A&Activities Activity Name Inter: A&Activities Inter: A&Activities Rolling Activities Rolling Activities Rolling Activities Rolling Activities Rolling Activities Rolling Acceleration of Sole Rolling Acceleration of Sole Rolling Excavation of Sole Sole Rolling Excavation of Sole Rolling Excavation of Sole CollingColling Acceleration CollingColling Acceleration Sole	Original Rem Duration D 469 140 21 27 11	ration Co 469 4 140 21 27 11 24 25	nplete 1.94% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 03-Nov-	20 114-1 20 11-4 20 21-3 20* 20-3 20* 12-0 20* 15-0 20* 11-4	Resources	Budgeted Labor Cost Rs10,665,350.00 Rs2,215,750.00 Rs9,5750.00 Rs0.00 Rs330,000.00 Rs840,000.00	Budgeted Nonlabor Cost Rs465,500.00 Rs465,500.00 Rs243,000.00 Rs243,000.00 Rs110,000.00	Budgeted Total Cost 1 Re319,594,450.00 Re329,750.00 Re329,750.00 Re3545,400.00 Re3545,400.00 Re3540,000.00	Standard 5 Day Workweek Standard 5 Day Workweek	
Layout: Class wity ID SHIVAL FORM A1000 A1021 A1031 A1041 A1041 A1041 A1041 A1041		Original Rem Duration Du 499 140 21 27 11 11 24 25 53	ration Co 469 4 140 21 27 11 24 25 53	Inplete 1.94% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 25-Nov- 100% 24-Aug- 100% 18-Nov- 100% 23-Dec-	20 14-1 20 11-4 20 21-3 10* 20-3 10* 20-3 10* 12-4 20* 15-4 20* 15-4 10 11-4 10 10-1	Resources O unskilled labour I consolid to truck, diesel I buck, compressor, bloor with supervisor, d I bubur with supervisor, diesel Compactor, bbour with supervisor, diesel	Budgeted Labor Cost Rs10,885,550.00 Rs2,215,750.00 Rs30,000.00 Rs330,000.00 Rs340,000.00 Rs750,000.00 Rs752,000.00	Budgeted Nonlabor Cost Rs4,649,500.00 Rs405,500.00 Rs20,000 Rs20,000 Rs110,000.00 Rs112,500.00 Rs112,500.00	Budgeted Total Cost Rs3(2,544,550 00 Rs2(2,77,650 00 Rs2(4,550 00 Rs454,000.00 Rs454,000.00 Rs454,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000.00 Rs40,000 Rs40,000.00 Rs40,000 Rs4	Standard S Day Workweek Standard S Day Workweek	
Civities R Layout: Class vity ID SHIVAL FORM A1001 A1021 A1031 A1031 A1041	esources Projects sic Schedule Layout Activity Name IK IX	Original Duration Du Rem Du 469 140 21 21 27 11 24 25	ration Co 469 4 140 21 27 11 24 25 53	Inplete O3-Aug 100% 03-Aug 100% 03-Nov 100% 24-Aug 100% 18-Nov	20 14-1 20 11-1 20 21-3 20 21-3 20 21-3 20* 20-3 20* 12-4 20* 15-4 20* 15-4 20* 15-4 20 11-1 10 10-1	Resources	Budgeted Labor Cost Rs10,865,350.00 Rs2,215,750.00 Rs0.00 Rs330,000.00 Rs340,000.00 Rs840,000.00 Rs840,000.00	Budgeted Nonlabor Cost Rs4(549,500.00 Rs485,500.00 Rs10,000.00 Rs112,500.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00	Budgeted Total Cost R519,591,450 00 Ra295,750 00 Ra545,400.00 Ra594,000.00 Ra545,400.00 Ra540,000.00 Ra1,002,500.00	Standard 5 Day Workweek Standard 5 Day Workweek	
Layout: Class vity D SHIVAL FORN A100 A102 A103 A101 A104 A104 A104 A104 A104 A104		Original Rem Duration Du 469 140 21 27 111 24 25 53 2	ration Co 469 4 140 21 27 11 24 25 53 2 2 2	Implete 194% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 25-Nov- 100% 24-Aug- 100% 18-Nov- 100% 23-Dec- 100% 05-Feb-2	20 14-1 20 11-K 20 21-3 20* 20-3 20* 20-3 20* 12-4 20* 15-4 20* 15-4 20* 10-1 10 10-1	Resources Inskilled labour excavator, truck, desel truck, compressor, labour with supervisor, d babarr with supervisor, d babarr with supervisor, desel skilled labour	Budgeted Labor Cost Rs10,835,350.00 Rs2,215,750.00 Rs330,000.00 Rs330,000.00 Rs340,000.00 Rs24,321,4600.00 Rs2,321,4600.00 Rs24,321,4600.00	Budgeted Nonlabor Cost Rs4(549,500.00 Rs485,500.00 Rs10,000.00 Rs112,500.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00	Budgeted Total Cost Rs19,594,450 00 Rs297,7650 00 Rs249,7650 00 Rs240,000 00 Rs240,000 00 Rs240,000 00 Rs2,221,600 00 Rs2,221,600 00 Rs2,201,600 00	Standard 5 Day Workweek Standard 5 Day Workweek	
ivities R. Layout: Class Classed Vity ID SHIVAL SHIVAL FORN A1000 A1022 A1031 A1034 A1040 PERM A1170 A1180	esources Projects ses Schedule Layout Activity Name Activity Nam Activity Nam Activity Name Activity Name	Original Rem Duration Do 489 140 21 27 11 24 25 53 53 2 2 2 2	ration Co 469 4 140 21 27 11 24 25 53 2 2 4	Inplete 194% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 25-Nov- 100% 24-Aug- 100% 23-Dec- 100% 23-Dec- 100% 05-Feb-2 100% 09-Feb-2	20 14-1 20 11-0 20 21-3 20 21-3 20 21-3 20* 20-3 20* 15-0 20* 15-0 10 10-1 11 06-1 11 10-1 10 26-0 10 26-0	Resources Constitled tabour Constitled tabour Constituted (Seel C	Budgeted Labor Cost Rs10,685,550.00 Rs2,215,750.00 Rs295,750.00 Rs330,000.00 Rs340,000.00 Rs340,000.00 Rs750,000.00 Rs72,000.00 Rs72,000.00 Rs73,600.00	Budgeted Nonlabor Cost Rs465,500.00 Rs405,500.00 Rs10,000.00 Rs110,000.00 Rs10,2500.00 Rs10,800.00 Rs0.00 Rs0.00	Budgeted Total Cost Re3(9):593,450,00 Re3295,750,00 Re354,000,00 Re354,000,00 Re354,000,00 Re32,002,500,00 Re32,022,500,00 Re32,000,00 Re37,2000,00 Re37,2000,00	Standard 6 Didy Workweek Standard 5 Day Workweek	
Layout: Class vity ID SHIVAL FORN A1000 A1021 A1030 A1011 A1041 PERM A1170 A1170 A1170 A1170		Original Duration Rem Duration 4699 140 211 27 111 24 25 53 2 2 2 2 4 4	ration Co 469 4 140 21 27 11 24 25 53 2 2 2 4 3	Implete 1946 03-Aug- 1000% 03-Aug- 100% 25-Sep- 100% 25-Sep- 100% 24-Aug- 100% 24-Aug- 100% 23-Dec- 100% 09-Feb- 100% 23-Dec-	20 14-1 20 11-0 20 21-3 20 21-3 20 21-3 20* 20-3 20* 15-0 20* 15-0 10 10-1 11 06-1 11 10-1 10 26-0 10 26-0	Resources 0 unskilled labour excavator, truck, diesel truck, compressor, labour with supervisor, d babour with supervisor, diesel skilled labour skilled labour skilled labour	Budgeted Labor Cost Rs10,855,550.00 Rs2,215,750.00 Rs330,000.00 Rs330,000.00 Rs330,000.00 Rs330,000.00 Rs750,000.00 Rs75,000.00 Rs75,000.00 Rs75,600.00	Budgeted Nonlabor Cost Rs464950000 Rs243,0000 Rs110,000.00 Rs112,500.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00	Budgeted Total Cest Res 19:594:450 00 Res 29:57:50 00 Res 54:000 00 Res 40:000 00 Res 40:000 00 Res 20:21:600 00 Res 20:000 00 Res 20:0000 00 Res 20:0000 00 Res 20:00000000000000000000000000000000000	Standard 5 Day Workweek Standard 5 Day Workweek	
ivities R. Layout: Class Classed SHIVAL FORN A100 A102 A100 A102 A101 A104 PERM A1170 A1171 A1171 A108 A108		Original Duration Rem Duration 469 140 21 140 27 11 24 25 53 2 2 2 4 3	ration Co 469 4 140 21 27 11 24 25 53 2 2 2 4 3	Inplete 194% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 25-Sep- 100% 25-Sep- 100% 18-Nov- 100% 23-Dec- 100% 05-Feb- 100% 05-Feb- 100% 23-Dec- 100% 23-Dec-	20 14-1 20 11-6 20 21-3 20 21-3 20* 20-3 10* 20-3 10* 12-6 20 11-6 11 06-1 11 10-1 10 26-6 100 25-6	Resources Constitled tabour Constitled tabour Constituted (Seel C	Budgeted Labor Cost Rs10,045,5450 00 Rs2,215,750 00 Rs3,20,600 00 Rs30,000 00 Rs30,000 00 Rs30,000 00 Rs32,31,600 00 Rs72,600 00 Rs72,600 00	Budgeted Nonlabor Cost Rs40;5500.00 Rs0.00 Rs10,000.00 Rs110,000.00 Rs110,000.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00 Rs0.00	Budgeted Total Cost R519,593,450,00 Ra529,7560,00 Ra545,400,00 Ra545,400,00 Ra54,000,00 Ra54,000,00 Ra54,000,00 Ra52,000,00 Ra72,800,00 Ra57,800,00 Ra56,000,00	Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R Layout: Class VFV D SHIVAL A100 A102 A103 A101 A104 A104 A104 A104 A104 A104 A104	esources Projects sic Schedule Layout Fiter: All Activities Activity Name Activity Name IX Totom WORKS Noudel Excavation of Sola Roudel Excavation of Sola Roudel Excavation of SolaBoulders ColmacTota Acad Form SolaBoulders Roudel Excavation of SolaBoulders ColmacTota Points SulaBoulders Ocommod Forms Sule Kinstone ColmacTota Points SulaBoulders Oconstruction of Collustert Bit Spent Construction of Callustert Bit Spent Construction of Collustert Bit Spent Construction of Collustert Bit Spent Construction of Collustert Bit Spent Construction Collaboulders Ando Chanimel Type Road Spec Drann Construction of Collaboulders Ando Chanimel Type Road Spec Drann Provoling And Poins Gabbadary Kit Stone	Original Duration Duration Duration 4/85 140 21 27 111 24 255 53 2 2 4 3 3 3	Co 459 4 140	Inplete 194% 03-Aug- 100% 03-Aug- 100% 25-Sep 100% 25-Sep 100% 25-Sep 100% 18-Nov 100% 23-Dec- 100% 05-Feb 100% 05-Feb 100% 23-Dec- 100% 23-Dec-	20 14-1 20 11-1 20 21-3 20 21-3 20 20-3 20* 20-3 20* 15-0 20* 15-0 20* 15-0 20* 15-0 10 10-1 11 06-1 11 06-1 10 26-0 20-2 25-0 20* 25-0 11 04-1	Resources Ounskilled labour Compactor, truck, desel truck, compressor, bloor with supervisor, d skilled labour skilled labour skilled labour skilled labour skilled labour skilled labour	Budgeted Labor Cest Rs10,050,550,00 Rs2,215,750,00 Rs330,000,00 Rs430,000,00 Rs4750,000,00 Rs4750,000,00 Rs4750,000,00 Rs472,000,00 Rs472,000,00 Rs475,000,00 Rs475,000,00 Rs450,000,00 Rs450,000,00 Rs450,000,00	Budgeted Nonlabor Cost Rs4.649,500.00 Rs40,000 Rs410,000.00 Rs410,000.00 Rs410,000.00 Rs410,000.00 Rs410,000.00 Rs40.00 Rs40.00 Rs40.00 Rs40.00 Rs40.00 Rs40.00 Rs40.00	Budgeted Total Cost Rs19,594,4500 Rs29,57500 Rs295,7500 Rs240,0000 Rs440,0000 Rs2,232,66000 Rs72,20000 Rs72,000000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,00000 Rs72,000000 Rs72,000000 Rs72,000000 Rs72,000000 Rs72,000000 Rs72,000000 Rs72,000000 Rs72,0000000 Rs72,000000000000000000000000000000000000	Standard 5 Day Workweek Standard 5 Day Workweek	
Initial Stress R. Layout: Class/vity D SHIVAL SHIVAL FORN A100 A102 A103 A101 A104 SHIVAL PERM A103 A101 A104 A104 A118 A107 A108 A106 A1168		Original Duration Duration 450 140 21 27 111 24 25 53 2 2 4 3 3 3	Co 489 4 140	Inplete 194% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 25-Sep- 100% 24-Aug- 100% 24-Aug- 100% 23-Dec- 100% 02-Feb-2	20 14-1 20 11-1 20 21-1 20* 20-3 10* 20-3 10* 20-3 10 11-16 10 10-11 10 26-12 11 10-11 10 26-12 10 25-12 11 04-11 10 25-12 11 04-11 10 31-12	Resources Unuskilled labour excavator, truck, diesel truck, compressor, labour with supervisor, d babour with supervisor, d babour with supervisor, d skilled labour	Budgeted Labor Cost Re12626-85000 Re32215,750 00 Re330,000.00 Re330,000.00 Re330,000.00 Re320,000 Re320,000 Re320,000 Re320,000 Re350,000 Re350,000 Re350,000 Re350,000 Re350,000 Re350,000 Re350,000 Re350,000 Re350,000 Re310,000 Re350,000 Re310,00	Budgeted Noniabor Cost Ra4(649.500 00 Ra243,000 00 Ra243,000 00 Ra112,500 00 Ra112,500 00 Ra0.00 Ra0.00 Ra0.00 Ra0.00 Ra0.00 Ra0.00 Ra0.00 Ra0.00 Ra0.00 Ra0.00 Ra0.00	Budgeted Total Cost Ra3,27,559,00 Ra3,27,7559,00 Ra54,500,00 Ra54,000,00 Ra54,000,00 Ra54,000,00 Ra72,000,00 Ra72,000,00 Ra72,000,00 Ra51,000,00 Ra51,000,00 Ra51,00,000 Ra51,00,000 Ra51,000,000 Ra51,000,000 Ra51,000,000 Ra51,000 Ra51,000,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,0000 Ra51,00000 Ra51,00000 Ra51,00000 Ra51,00000 Ra51,00000 Ra51,00000 Ra51,00000 Ra51,000000 Ra51,00000 Ra51,00000 Ra51,00000 Ra51,00000 Ra51,000000	Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R Layout: Class VPy D SHIVAL P FORM A1020 A1021 A1031 A1041 A1041 A1041 A1041 A1041 A1041 A1051 A1161 A16	esources Projects aic Schedule Layout Piter: All Activities Activity Name UK IX	Original Duration Pattern Duration 460 24 21 27 111 24 25 3 2 2 4 3 3 3 4 4	Co 459 4 140 - 21 - 27 - 111 - 24 - 53 - 2 - 2 - 3 - 3 - 4 - 5 -	Install Osciliaria 1944 Osciliaria 1005 Osciliaria 1005 Osciliaria 1005 Osciliaria 1005 Osciliaria 1005 Osciliaria 1005 Osciliaria 1006 Osciliaria 1007 Osciliaria 1008 Osciliaria 1009 Osciliaria 1000 Osciliaria	20 14-1 20 11-1 20 21-1 20* 20-3 10* 20-3 10* 11-10 20 11-10 10 10-11 10 25-00 10 25-00 10 25-00 11 04-11 10 25-00 11 04-11 10 31-00 10 31-00 10 31-00 10 31-00 10 31-00	Resources Constituted tabour Constituted tabour Constituted tabour Construction, compression, babour with supervisor, d ablocur with supervisor, diseal ablied tabour Skilled tabour S	Budgeted Labor Cost Res2,215,750 00 Res2,215,750 00 Res30,000 00 Res30,000 00 Res30,000 00 Res30,000 00 Res20,1600 00 Res20,000 00 Res20,000 00 Res10,000 00 Res20,000 00 Res20,0000 Res20,000 Res20,000 Res20,000 Res20,000 Res20,000 Res20,00	Budgeted Nonlabor Coat Rs4,649,500 00 Rs40,500 00 Rs10,000 00 Rs10,000 00 Rs10,000 00 Rs10,000 00 Rs0,00 Rs0,00 Rs0,00 Rs0,00 Rs0,00 Rs0,00 Rs0,00 Rs0,00 Rs0,00 Rs0,00 Rs0,00	Budgeted Total Cost Re3.927.75.00 Re3.227.75.00 Re3.227.75.00 Re3.245.4000.00 Re3.002.500.00 Re3.227.600.00 Re3.227.600.00 Re3.237.600.00 Re3.200 Re3.20	standard 5 Day Workweak Standard 5 Day Workweak	
tivities R Layout: Class Way D SHIVAL SHIVAL SHIVAL SHIVAL SHIVAL A100 A100 A100 A100 A100 A100 A100 A1		Digital Ref Duration Du 400 21 21 21 21 21 21 21 22 4 3 3 2 2 2 4 3 3 3 3 4 4 5 5	rration Co 469 4 140 21 27 111 24 25 33 2 2 2 4 3 3 3 4 4 5 5 5	Implete O3-Aug- 19342 03-Aug- 100% 03-Aug- 100% 23-Sep- 100% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 03-Aug- 100% 24-Aug- 100% 24-Aug- 100% 25-Feb- 100% 23-Dec- 100% 24-Dec- 100% 24-Dec- 100% 24-Da-	20 14-1 20 11-0 20 21-3 20* 20-3 20* 15-0 20* 15-0 20* 15-0 20* 15-0 20* 15-0 10 10-1 11 06-1 10 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 25-0 20* 31-0 20* 31-0 20* 31-0	Resources Resource Resource Resource Resource Resource Resource Resourc	Budgeted Labor Cest 2410,020,01000 Re22,215,750 00 Re32,215,750 00 Re32,000 00 Re32,000 00 Re32,000 00 Re32,000 00 Re32,000 00 Re32,000 00 Re32,000 00 Re32,000 00 Re310,000 00 Re310,000 Re310,000 00 Re310,000 00 Re310,000 Re310,000 00 Re31	Budgeted Noniabor Cost Rs465,500 00 Rs465,500 00 Rs10,000 00 Rs10,000 Rs10,000 Rs10,000 Rs0,0	Budgeted Total Cost Res 19,591,4500 Res 2,77,550 00 Res 24,500 00 Res 40,000 00 Res 1,002,500 00 Res 7,000 00 Res 7,000 00 Res 7,000 00 Res 7,000 00 Res 7,000 00 Res 100,000 00 Res 112,000 00 Res 112,000 00 Res 112,000 00 Res 112,000 00 Res 115,000 00 Res 10,000 00 Res	Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R. 4 249047 Class ivity ID SHIVAL FORM A1000 A1020 A102 A103 A104 A104 A104 A104 A105 A104 A105 A105 A106 A106 A116 A106 A1150	Esources Projects aic Schedule Layout Fiter: All Activities Activity Name Activity Name IX IX MOTON WORKS Juncite CREARANCE INUNUE CREARANCE ROUGH EXCAVATION OF PARD ROCKS BY DRILLING ROUGH EXCAVATION OF PARD ROCKS BY DRILLING COMMACTION AND FARING SUB KIN STONE ROUGH EXCAVATION OF SOLTSOL COMMACTION AND FARING NUMB KINSTONE ROVDONG AND FORM DELINATOR MOMM CONSTRUCTION OF CULVERTS IN SPAN CONSTRUCTION OF CULVERTS IN SPAN CONSTRUCTION OF CULVERTS IN SPAN CONSTRUCTION OF RIMIN BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT CONSTRUCTION OF RAMI BREAST WALL SIM HEIGHT	Original Duration Duration 4600 24 211 21 111 24 253 2 2 4 3 3 3 3 4 5 5 5 6 6	rration Co 459 4 140 21 27 27 25 53 2 2 4 3 3 3 3 3 4 4 4 5 5 5 5 5 6	Inpete Inpete 19.94 03-Auge 100% 03-Auge 100% 03-Auge 100% 03-Auge 100% 25-Sep 100% 25-Sep 100% 24-Auge 100% 24-Mage 100% 23-Dec 100% 05-Feb 100% 23-Dec	14-12 20 14-12 20 11-6 20 21-7 20 21-7 20 21-7 20 12-2 201 12-2 202 15-7 12-201 11-6 11 06-7 11 06-7 12 25-7 14 04-1 10 31-4 10 31-4 10 31-4 11 06-1	Resources Inskilled labour Unskilled labour Unuck, compressor, Nabor With supervisor, d babour with supervisor, diseal Unuck, compressor, Nabor With supervisor, d babour with supervisor, diseal skilled labour	Budgeted Labor Cest Re10.026,350 00 Rea2.215,750 00 Re32.00,750 00 Re33.00,000 00 Re33.00,000 00 Re32.000,000 Re32.000,000 Re32.000,000 Re32.000,000 Re32.000,000 Re310,000 00 Re312,000,000 Re312,000,000 Re312,000,000 Re312,000,000 Re312,000,000	Budgeted Nonlabor Cost Rs0(e92,500 00 Rs465,500 00 Rs0,00 Rs10,000 00 Rs10,2500 00 Rs0,00 Rs0	Budgeted Total Cost Rs3(95944500 Ra327,75500 Ra529,75500 Ra529,400000 Ra549,40000 Ra549,400000 Ra549,400000 Ra72,00000 Ra72,200000 Ra51,002,50000 Ra51,000000 Ra5100,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,000000 Ra5120,000000 Ra5120,000000 Ra5120,00000000000000000000000000000000000	Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R Layout: Class ivity D SHIVAL FORM A 100 A 102 A 103 A 100 A 102 A 103 A 100 A 102 A 103 A 100 A 104 A 105 A 116 A 1		Original Ren Duration Du 440 140 21 21 27 71 11 25 23 2 24 3 3 3 4 5 5 6 5 5	rration Co 469 4 140 - 27 27 24 24 25 53 2 2 4 3 3 3 3 4 4 5 5 6 5 5	Instelle Instelle 100% 03.Aug- 100% 04.Aug- 100% 05.Feb- 100% 03.Dec- 100% 03.Dec- 100% 03.Dec- 100% 03.Dec- 100% 03.Dec- 100% 23.Dec- 100% 23.Dec- 100% 23.Dec- 100% 23.Dec- 100% 23.Dec- 100% 23.Dec- 100% 23.Dec- 100% 23.Dec- 100% 23.Dec- 100% 30.Dec-	14-12 20 14-12 20 11-6 20 11-6 20 11-6 20-10* 20-3 20-11 12-2 20-11 14-1 10 20-1 11 10-1 10 25-6 11 04-1 10 14-1 10 14-1 10 25-6 10 25-1 10 14-1 10 14-1 10 14-1 11 14-1 12 14-1 14 14-1 15 14-1 16 14-1	Resources Constilled labour Compressor, bloor with supervisor, d Solard Shour with supervisor, d Solard Shour with supervisor, d Solard Shour Solard S	Budgeted Labor Cest 22,215,750 00 Rs22,215,750 00 Rs23,000 00 Rs430,000 00 Rs750,000 00 Rs750,000 00 Rs750,000 00 Rs35,000 00 Rs35,000 00 Rs450,000 00 Rs152,000 00 Rs152,0000 Rs152,000 00 Rs152,000 00 Rs152,000 00 Rs152,000 00	Budgeted Noniabor Costi Radi(249,50000 Rade5,50000 Rad00 Rat10,000 00 Rat10,000 00 Rat10,000 00 Rat0,0	Budgeted Total Cost Res 10,503,4500 Res 2,77,550 00 Res 24,500,00 Res 40,000 Res 40,000 Res 1,002,500,00 Res 7,000 00 Res 7,000 00 Res 7,000 00 Res 7,000 00 Res 7,000 00 Res 10,000 00 Res 112,000 00 Re	Standard 5 Day Workweek Standard 5 Day Workweek	
tivities R. 4000		Original Duration Duration 4600 24 211 21 111 24 253 2 2 4 3 3 3 3 4 5 5 5 6 6	rration Co 459 4 140 21 27 7 111 24 25 53 2 2 4 3 3 3 4 4 5 5 5 5 5 5 5 5 5 5 5 5 5	Inpete Inpete 19.94 03-Auge 100% 03-Auge 100% 03-Auge 100% 03-Auge 100% 25-Sep 100% 25-Sep 100% 24-Auge 100% 24-Mage 100% 23-Dec 100% 05-Feb 100% 23-Dec	14-12 20 14-2 20 11-6 20 21-3 20 21-3 20 21-3 20 21-3 20 21-3 20 21-3 20-10* 20-3 20 12-2 20 11-6 11 06-1 11 06-2 10 25-3 10 25-4 10 04-4 10 04-3 11 06-1 12 30-1 13 04-1 10 04-3	Resources Constilled labour Compressor, bloor with supervisor, d Solard Shour with supervisor, d Solard Shour with supervisor, d Solard Shour Solard S	Budgeted Labor Cest Re10.026,350 00 Rea2.215,750 00 Re32.00,750 00 Re33.00,000 00 Re33.00,000 00 Re32.000,000 Re32.000,000 Re32.000,000 Re32.000,000 Re32.000,000 Re310,000 00 Re312,000,000 Re312,000,000 Re312,000,000 Re312,000,000 Re312,000,000	Budgeted Nonlabor Cost Rs0(e92,500 00 Rs465,500 00 Rs0,00 Rs10,000 00 Rs10,2500 00 Rs0,00 Rs0	Budgeted Total Cost Rs3(95944500 Ra327,75500 Ra529,75500 Ra529,400000 Ra549,40000 Ra549,400000 Ra549,400000 Ra72,00000 Ra72,200000 Ra51,002,50000 Ra51,000000 Ra5100,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,00000 Ra5120,000000 Ra5120,000000 Ra5120,000000 Ra5120,00000000000000000000000000000000000	Standard 5 Day Workweek Standard 5 Day Workweek	

Bar Representation of Scheduled activities

Hilly road mapping and holistic management to visualize and plan construction: A case study in Himalayan region



Conclusions:

In this Paper a case study upon a newly planned hilly road located in Uttarakhand state amongst the Himalayan region of India is discussed. Using modern surveying equipment the data is collected from the field, which is further reproduced in 3D and 2D terrain maps of different configuration via Surfer software. Estimation of the whole project considering various aspects of constructions as per the guidelines of Ministry of road transport India and BOQ CPWD Uttarakhand are generated via Excel and Primavera software. Results published here of the case study not only establishes the construction management principles but also present a statistical data for further study. The current project is performed assuming the static coordinates whereas real– time coordinates must be considered as input in total station for more accuracy.

Surveying done for construction of roadway is not just about the preparation of the road, but also about the design of the roadway. Land surveys help one to determine the roadway design, materials required and the construction method to be applied for that particular project. The field data presented in the paper provides a

necessary platform to facilitate decision making and management of road construction. Efficiently done scheduling of the road construction yields a 3-month faster construction time as compared to 18 months sanctioned time of the project. Total estimated cost of the project is based on the current rates provided by govt authorities and is subjected to change; however author believes furnishing of cost data will help designers a great deal to optimize the cost of their running projects.

References:

- 1. Gowtham P, Mahendran, Vignesh R, Priya R and Dr. Vijayalakshmi (2015). "Widening and renovation of hill road pavement from Doddabetta to Kattabettu in the Nilgiri district". *Innovation and Applied Studies*.
- 2. You Runwei (2014). "Safety Design on small radius curve of Mountain road" *Applied Mechanics and Materials 2014*.
- 3. Joshi Anil Kumar, Joshi Chitra, Singh Mridu, Singh Vikram (2014). "Road traffic accidents in hilly regions of northern India: What has to be done?" *World journal of emergency medicine*.
- 4. Kadiyali LR. "Highway Engineering". Khanna Publishing House; 2017.
- 5. Xiaobin Zhu, Junmin Shen and Xiao Zhang (2013). "Longitudinal Cracking Reasons and Prevention of Widening Pavements of Old Roads". *Applied Mechanics and materials*.
- 6. Weng Xiaolin and Wang Wei (2011). "Influence of differential settlement on pavement structure of widened roads based on large-scale model test" *Journal of Rock Mechanics and Geotechnical Engineering2011*.
- 7. Ling Jianming, Qian Jinsong, and Huang Qinlong (2007). "Failure Mechanism and Design Criterion for Low-Volume Roads Subgrade Widening." *Transportation Research Record: Journal of the Transportation Research Board, No1989.*
- 8. Wang Hao and Huang Xaioming (2006). "The study of ground and Embankment treatment techniques in Road Widening." *Pavement Mechanics and Performance, ASCE*.